

- ① SUPERPAVE ASPHALT MIXTURE DESIGN, WEARING COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 9.5 MM MIX, 1 1/2" DEPTH, SRL-H
 - ② SUPERPAVE ASPHALT MIXTURE DESIGN, BINDER COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 19.0 MM MIX, 2 1/2" DEPTH
 - ③ SUPERPAVE ASPHALT MIXTURE DESIGN, BASE COURSE, PG 64S-22, 0.3 TO < 3 MILLION ESALS, 25.0 MM MIX, 4" DEPTH
 - ④ SUBBASE 8" DEPTH (NO. 2A)
- NOTE: APPLY ASPHALT TACK COAT BETWEEN ALL ASPHALT PAVEMENT LAYERS

GENERAL NOTES:

CONSTRUCT PROJECT IN ACCORDANCE WITH PUBLICATION 408 DATED 2020 AND CONTRACT SPECIAL PROVISIONS.

ALL WORK IS TO BE CONFINED WITHIN THE EXISTING HIGHWAY RIGHT-OF-WAY AND/OR PROPERTY OF THE COMMONWEALTH OF PENNSYLVANIA.

FURNISH, ERECT, PLACE AND MAINTAIN TRAFFIC CONTROL SIGNS AND DEVICES, AND MAINTAIN TRAFFIC DURING HOURS OF CONSTRUCTION AND AT ALL OTHER TIMES IN ACCORDANCE WITH THE METHODS INDICATED ON THE DRAWINGS AND THE FOLLOWING:


SPECIAL PROVISIONS OF THE CONTRACT
 PUBLICATION 213, TEMPORARY TRAFFIC CONTROL GUIDELINES
 PA CODE, TITLE 67, CHAPTER 212, OFFICIAL TRAFFIC CONTROL DEVICES
 PENNDOT PUBLICATION 35, APPROVED CONSTRUCTION MATERIALS (BULLETIN 15)
 PENNDOT PUBLICATION 46, TRAFFIC ENGINEERING MANUAL
 PENNDOT PUBLICATION 408, LATEST EDITION
 PENNDOT PUBLICATION 111M, TRAFFIC CONTROL PAVEMENT MARKING AND SIGNING STANDARDS
 PENNDOT PUBLICATION 236, HANDBOOK OF APPROVED SIGNS
 MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), 2009

INSTALL ALL MARKING AND DELINEATORS IN ACCORDANCE WITH THE CURRENT PUBLICATION STANDARDS (PUB. 111M, TC-8600 SERIES)



**PROPOSED ACCELERATION LANE
 SR 93 (BERWICK HAZLETON HIGHWAY)
 NESCOPEK TOWNSHIP, LUZERNE COUNTY**

CONCEPTUAL PLAN
 NESCOPEK BRIDGE PACKAGE



DATE
 DECEMBER 2021

FIGURE
 FIGURE